



May 8, 2026

### Addendum No. 1 for Open Ditch Repairs, Drainage District No. 4

This Addendum No. 1 is issued to revise bid quantities and for modifications of specifications and construction methods. The updated portion of the spec is shown in bold. All revised quantities to date are shown in bold.

This Addendum replaces the existing Proposal Attachment: Part C – Bid Items, Quantities, and Prices and shall be used for the bidding. The original Proposal Attachment will not be accepted.

This Addendum shall become part of the Contract Documents. Bidders are encouraged to review this Addendum in full prior to submitting bids. Except as modified herein, all other portions of the Plans and Specifications shall remain in full force and effect.

---

#### Division 4- Storm Sewers

#### Section 4030- Pipe Culverts

##### K. Tile Outlet:

1. Measurement: Measurement will be in linear feet for the specified type and size of Tile Outlet Pipe.
2. Payment: Payment will be at the unit price per linear foot of each type and size of pipe.
3. Includes: Unit price includes all labor and materials to connect to an existing tile line, furnish and install a new outlet pipe section (CMP, 20 ft as specified), furnish and install all necessary excavation, bedding, and backfill. Includes relaying or repairing the existing tile to make a good concrete collared connection. **Any length of HPDE tile used to make a good connection is a separate bid item. A log of all HDPE used per connection will need to be submitted.** A time stamped and geo-located photo of each connection to the existing tile and a log of all connections is to be submitted to engineer prior to payment. Payment includes installing a 2" x 10' tall PVC pipe placed over an 8' steel T-post to serve as a marker. No outlet or inlet erosion protection is required.

#### Division 9- Site Work and Landscaping

#### Section 9010- Seeding

##### E. Open Ditch Slope Permanent Seeding (Hydraulic Seeding):

1. Measurement: Measurement will be in stations.
2. Payment: Payment will be at the unit price per station. No actual measurement will be taken.

3. Includes: Unit price includes, but is not limited to, furnishing, seeding, and fertilizing the ditch banks via hydraulic seeding. **Mulching is not required for Hydraulic Seeding.**

## ***PROPOSAL ATTACHMENT: PART C – BID ITEMS, QUANTITIES, AND PRICES***

This is a UNIT BID PRICE CONTRACT. The bidder must provide the Unit Bid Price(s) for Part C – Bid Items, Quantities, and Prices. The Unit Price shall govern the total amount for each bid item. The total of the Bid shall be used for determining the sufficiency of the bid security.

<b>BID ITEMS</b>					
ITEM NO.	DESCRIPTION	ESTIMATED UNITS	UNIT	UNIT PRICE	AMOUNT
101	OPEN DITCH EXCAVATION	50,800	CY	\$	\$
102	SPOIL LEVELING	244	STA	\$	\$
103	OPEN DITCH SLOPE TEMPORARY COVER CROP SEEDING	244	STA	\$	\$
104	OPEN DITCH SLOPE PERMANENT SEEDING (HYDRAULIC SEEDING)	244	STA	\$	\$
105	SPOIL TILLAGE & ROCK PICK UP	244	STA	\$	\$
106	OPEN DITCH SPOIL COVER CROP SEEDING	244	STA	\$	\$
107	TILE OUTLET, 8" CMP	440	LF	\$	\$
108	TILE OUTLET, 12" CMP	640	LF	\$	\$
109	TILE OUTLET, 15" CMP	520	LF	\$	\$
110	TILE OUTLET, 18" CMP	240	LF	\$	\$
111	TILE OUTLET, 24" CMP	40	LF	\$	\$
112	TILE OUTLET, 36" CMP	60	LF	\$	\$
113	TILE OUTLET, 42" CMP	60	LF	\$	\$
114	SURFACE DRAIN PIPE, 18" CMP	1,790	LF	\$	\$
115	SURFACE DRAIN PIPE, 24" CMP	360	LF	\$	\$
116	SURFACE DRAIN PIPE, 30" CMP	90	LF	\$	\$
117	CLEARING & GRUBBING	1	LS	\$	\$
118	FENCE REMOVAL	1,900	LF	\$	\$
119	ROCK CHUTE	1	EA	\$	\$
120	RIPRAP, CLASS E	220	TNS	\$	\$
121	CONSTRUCTION ACCESS DRIVEWAY	1	EA	\$	\$
122	SEDIMENT BAFFLE	1	LS	\$	\$
123	MOBILIZATION	1	LS	\$	\$
124	3"-6" SINGLE-WALL CORRUGATED HDPE PIPE	220	LF	\$	\$
125	8" – 10" DUAL-WALL HDPE PIPE	320	LF	\$	\$
126	12" DUAL-WALL HDPE PIPE	260	LF	\$	\$
<b>TOTAL BID</b>					<b>\$</b>

**NOTE:**

Due to the inherent variability of Drainage District construction, the quantities provided herein are estimates for bidding purposes only. Final quantities and payment will be based on actual measurements and conditions encountered in the field. Quantity changes that amount to 20% or less of the amount bid shall not affect the unit bid price.

---

**Reminder:**

**Bids Due:**


Thursday, May 14, 2026  
1:00 P.M.

**Location:** Hamilton County Auditor's Office


Hamilton County Courthouse, 2300 Superior Street, Suite 2, Webster City, IA 50595

Sincerely,

AgriVia



Jacob Hagan, P.E.  
jacob.agrivia@gmail.com  
712-250-4318



Tyler Buman  
tyler.agrivia@gmail.com  
712-579-5296